

## ADDENDUM NO. 1

---

**Attention:** Terry Calder

**Address:** 1299 Oxford St E #5C5  
London, ON N5Y 4W5

**Date:** November 20, 2018

**Project #:** CE-4125

**Project:** McNay MUA Replacement

**Cc.** ---

Please amend the drawings and specifications for the above noted project as described below. Identify this addendum on the tender form to insure a complete tender form.

---

### 1. MECHANICAL

- 1.1. Insulate and heat trace condensate piping from MUA-101 to roof.
- 1.2. Offset and extend existing plumbing vents to maintain 11.5ft clearance from intake of MUA.
- 1.3. Existing sanitary risers are cast iron pipe.
- 1.4. Internal insulation within top floor to remain existing, external and internal insulation for ductwork on roof to be new.
- 1.5. Add to specification for surface finishes of exterior ductwork: "Zero permeability, self-adhesive laminate exterior insulation cladding, minimum 5 ply, 25 lb puncture rating, service temperature rating from -94°F to 300°F (-70°C to 148°C). 3M Ventureclad 1577CW\* or equal."

### 2. STRUCTURAL

- 2.1. Contractor to carry \$10,000.00 allowance for make-up air servicing platforms.
- 

*END OF ADDENDUM No. 1*